

07-25-00

A

UTILITY PATENT APPLICATION TRANSMITTAL
(Large Entity)

(Only for new nonprovisional applications under 37 CFR 1.53(b))

Docket No.
DE919950047US2

Total Pages in this Submission

TO THE ASSISTANT COMMISSIONER FOR PATENTSBox Patent Application
Washington, D.C. 20231

Transmitted herewith for filing under 35 U.S.C. 111(a) and 37 C.F.R. 1.53(b) is a new utility patent application for an invention entitled:

**METHODOLOGY FOR GENERATING ACCESSING FUNCTIONS FOR PROGRAMMED
EXECUTION OF PANEL-DRIVEN BUSINESS APPLICATIONS**

and invented by:

Andrea Schmidt and Ute Twisselmann

If a CONTINUATION APPLICATION, check appropriate box and supply the requisite information:

☒ Continuation ☐ Divisional ☐ Continuation-in-part (CIP) of prior application No.: 08/765,745

Which is a:

☐ Continuation ☐ Divisional ☐ Continuation-in-part (CIP) of prior application No.:

Which is a:

☐ Continuation ☐ Divisional ☐ Continuation-in-part (CIP) of prior application No.:

Enclosed are:

Application Elements

1. ☒ Filing fee as calculated and transmitted as described below
2. ☒ Specification having 56 pages and including the following:
 - a. ☒ Descriptive Title of the Invention
 - b. ☒ Cross References to Related Applications (if applicable)
 - c. ☐ Statement Regarding Federally-sponsored Research/Development (if applicable)
 - d. ☐ Reference to Microfiche Appendix (if applicable)
 - e. ☒ Background of the Invention
 - f. ☒ Brief Summary of the Invention
 - g. ☒ Brief Description of the Drawings (if drawings filed)
 - h. ☒ Detailed Description
 - i. ☒ Claim(s) as Classified Below
 - j. ☒ Abstract of the Disclosure

UTILITY PATENT APPLICATION TRANSMITTAL
(Large Entity)

(Only for new nonprovisional applications under 37 CFR 1.53(b))

Docket No.
DE919950047US2

Total Pages in this Submission

Application Elements (Continued)

3. ☒ Drawing(s) *(when necessary as prescribed by 35 USC 113)*
- a. ☐ Formal Number of Sheets _____
- b. ☒ Informal Number of Sheets 11
4. ☒ Oath or Declaration
- a. ☐ Newly executed *(original or copy)* ☐ Unexecuted
- b. ☒ Copy from a prior application (37 CFR 1.63(d)) *(for continuation/divisional application only)*
- c. ☒ With Power of Attorney ☐ Without Power of Attorney
- d. ☐ DELETION OF INVENTOR(S)
Signed statement attached deleting inventor(s) named in the prior application,
see 37 C.F.R. 1.63(d)(2) and 1.33(b).
5. ☒ Incorporation By Reference *(usable if Box 4b is checked)*
The entire disclosure of the prior application, from which a copy of the oath or declaration is supplied under
Box 4b, is considered as being part of the disclosure of the accompanying application and is hereby
incorporated by reference therein.
6. ☐ Computer Program in Microfiche *(Appendix)*
7. ☐ Nucleotide and/or Amino Acid Sequence Submission *(if applicable, all must be included)*
- a. ☐ Paper Copy
- b. ☐ Computer Readable Copy *(identical to computer copy)*
- c. ☐ Statement Verifying Identical Paper and Computer Readable Copy

Accompanying Application Parts

8. ☐ Assignment Papers *(cover sheet & document(s))*
9. ☐ 37 CFR 3.73(B) Statement *(when there is an assignee)*
10. ☐ English Translation Document *(if applicable)*
11. ☒ Information Disclosure Statement/PTO-1449 ☒ Copies of IDS Citations
12. ☐ Preliminary Amendment
13. ☒ Acknowledgment postcard
14. ☒ Certificate of Mailing
- ☐ First Class ☒ Express Mail *(Specify Label No.):* EJ896416485US

UTILITY PATENT APPLICATION TRANSMITTAL
(Large Entity)

(Only for new nonprovisional applications under 37 CFR 1.53(b))

Docket No.
DE919950047US2

Total Pages in this Submission

Accompanying Application Parts (Continued)

15. ☐ Certified Copy of Priority Document(s) *(if foreign priority is claimed)*


16. ☐ Additional Enclosures *(please identify below):*

Fee Calculation and Transmittal

CLAIMS AS FILED

For	#Filed	#Allowed	#Extra	Rate	Fee
Total Claims	45	- 20 =	25	x \$18.00	\$450.00
Indep. Claims	6	- 3 =	3	x \$78.00	\$234.00
Multiple Dependent Claims (check if applicable) <input type="checkbox"/>					\$0.00
BASIC FEE					\$690.00
OTHER FEE <i>(specify purpose)</i>					\$0.00
TOTAL FILING FEE					\$1,374.00

- ☐ A check in the amount of _____ to cover the filing fee is enclosed.
- ☒ The Commissioner is hereby authorized to charge and credit Deposit Account No. **09-0463** as described below. A duplicate copy of this sheet is enclosed.
- ☒ Charge the amount of **\$1,374.00** as filing fee.
- ☒ Credit any overpayment.
- ☒ Charge any additional filing fees required under 37 C.F.R. 1.16 and 1.17.
- ☐ Charge the issue fee set in 37 C.F.R. 1.18 at the mailing of the Notice of Allowance, pursuant to 37 C.F.R. 1.311(b).


Signature

Floyd A. Gonzalez, Reg. 26,732
IBM Corporation
Intellectual Property Law
2455 South Road, P386
Poughkeepsie, New York 12601
(845) 433-1163
Fax: (945) 432-9786

Dated: July 24, 2000

CC:

Docket No: DE919950047US2

METHODOLOGY FOR GENERATING
ACCESSING FUNCTIONS FOR
PROGRAMMED EXECUTION OF
PANEL-DRIVEN BUSINESS
APPLICATIONS


APPLICATION FOR
UNITED STATES LETTERS PATENT

Express Mail Label No: EJ896416485US

Date of Deposit: July 24, 2000

I hereby certify that this correspon-
dence is being deposited with the
United States Postal Service as
Express Mail Post Office to Addressee
Service under 37 CFR 1.10 on the date
indicated above and is addressed to
Box Patent Application, Commissioner
of Patents and Trademarks, Washington,
D. C. 20231.

Susan L. Nelson



I N T E R N A T I O N A L B U S I N E S S M A C H I N E S
C O R P O R A T I O N

004204264260

METHODOLOGY FOR GENERATING
ACCESSING FUNCTIONS FOR PROGRAMMED EXECUTION
OF PANEL-DRIVEN BUSINESS APPLICATIONS

Cross-Reference to Related Applications

- 5 This is a continuation of application Serial No. 08/765,745 filed
January 7, 1997.

1 Background of the Invention

1.1 Field of the Invention

004200 10 The present invention relates to a method allowing and guiding
the integration and migration of Business Applications (BA)
executed on a data processing system into modern environments. In
particular the present invention relates to a method of providing
access to BAs executed on a data processing system wherein said
BAs hitherto offer their services interactively controlled by a
15 multitude of BA panels and wherein said BAs may display
succeeding BA panels dependent on user interactions, user
specified data and the contents of any kind of data base the BA
is operating on.

1.2 Description and Disadvantages of Prior Art

- 20 Exploiters of information technology as well as information
technology itself are confronted with a new dimension of
flexibility and adaptability challenges for software supporting
and controlling their business. Of course the software
development techniques are confronted with these requirements
25 too. On one hand business initiatives are the creators of these

demands on the other hand information technologies themselves are the driving forces.

Companies are coping with new and changing market requirements. Improved customer services and time-to-market are key differentiators. Globalization of markets, organizational changes like decentralization, new cooperations require new business structures and concepts. As an answer to these challenges companies are attempting to re-engineer the underlying business processes to a serious extend. Business application software encompassing a huge spectrum of different application types, like Online Transaction Processing Applications (OLTP), data base applications etc., has an important supporting and enabling element in this arena it has to follow these tracks. The situation is even worse as information technologies themselves undergo drastic changes by offering new technologies like Client/Server, multi-media and object-oriented (OO) technologies.

Various approaches are known as attempt to integrate, to migrate or to adapt existing BAs to these changes in general and to OOT in specific, as OOT becomes more and more important and is believed to be the unifying approach for accessing other types of new technology.

If the origins of a given application are dated back many years and sometimes even more than a decade and if technologies have been subject of dramatic evolution, a first impulse might suggest to abandon these types of legacy applications, as an adaptation with respect to the new technologies like client/server concepts etc., these applications haven't been prepared for, seems hopeless.

No doubt that this kind of approach might be reasonable in certain situations. The decision to "throw away" a legacy

application often is a hasty response. Searching for alternatives allowing to "reuse" the legacy applications is worthwhile as they contain valuable knowledge on the business they are supporting. Many person-years would have to be spent for their

5 re-implementation. Also as many companies rely in a vivid sense on their business supporting applications such discontinuities may not be acceptable and more evolutionary approaches may be favorable instead.

10 Modernization of legacy applications by restructuring could be an alternative attitude. As a result this concept often requires great investment in the old application itself whereas the "visible" effects of modern technologies are very modest compared to the overall effort. Sometimes restructuring an application
15 actually led to a completely new implementation. If on the other hand this "hidden" re-implementation is to be avoided typically one is limited with respect to the freedom of designing the characteristics of the new application structure.

Another approach in this arena, called "face-lifting",
20 concentrates on the user interfaces of existing BA exclusively. This type of approach is limited to just renovate the panel driven user interfaces attempting to realize user interfaces showing more proximity with modern graphical user interfaces available on personal workstations. An important flaw of this
25 type of approach is its inability to modify the execution sequence inherent in the existing panel flow.

1.3 Objective of the Invention

The invention is based on the objective to generate and execute access structures for executing BAs, which offer their services
30 interactively controlled by a multitude of BA panels, avoiding the handling of the multitude of individual panels explicitly by

a user. The same method should hold also for the case that the BAs are executed on a remote data processing system, i.e. not on the same system requesting the services of the BAs.

2 Summary and Advantages of the Invention

5 The objective of the invention offers the benefit to automatically generate the Transaction Method (TM) procedures for accessing and programmed execution of a Business Application (BA). The BA hitherto offers its services by a sequence of panels and might have never been prepared for a programmed execution.

10 The TM generation process is based on a description of the panels currently used and processed by the BA to interact with its exploiter. A generated TM performs, just by being called, the execution of at least a part of a BA. A TM then operates autonomously and executes and controls the BA, handling,

15 invisible to its caller, the panels processed by the BA. The TM automatically enters all required input parameters into the correct positions of the BA panels and returns the output information delivered by BA panels to its callers. A BA which may have never been prepared for programmed execution now can be

20 processed by calling a TM and thus offers its services to other programs. It might be even possible that the same application may be exploited by certain users via the traditional panel driven user interfaces.

Additional advantages of the invention prepares the basis for

25 automatic TM generation by proposing a method of setting up said BA panel description being the input to the TM generation process. Having available a detailed description of each BA panel, also called a BA message, in form of a Transaction Record (TR) and the sequence of BA messages as processed by the BA in

30 form of User Interaction Graph (UIG) allows to generate TMs,

which, when executed, are able to handle the BA messages in an adequate sequence.

Additional advantages of the invention enable the generated TMs not only to fill data into or extract data from BA messages but also to select a particular action to launch the BA to process a particular next BA message sent as a response.

Additional advantages of the invention provide that the TMs can be generated such that they have a precise knowledge on all aspects, like type, length, position, input/output character and so forth, of each individual BA message element and parameter. This knowledge is fundamental to the TM capability of autonomously executing and controlling the BA.

Additional advantages of the invention provide that exploiters of the invention are offered the freedom of choice to either gather the information for the BA message description interactively or to extract the information by parsing the BA message implementations available from the BA execution environment. The parsing approach significantly eases and speeds up the process of modelling and defining the BA message descriptions.

Additional advantages of the invention provide that the automatic TM generation process is equipped with information allowing to determine which BA messages sequences are grouped together to be handled by TMs. The various indication of TRs can be used to define the begin or end of an individual TM.

Additional advantages of the invention provide decision rules to the automatic TM generation process for decomposing the whole UIG into individual BA message execution units and to create separate TMs for each execution unit.

Additional advantages of the invention provide decision rules to the automatic TM generation process for determining the input and output parameters of the TMs to be generated.

5 Additional advantages of the invention provide for the execution of the generated TMs and the BA, which is controlled by the TMs, on remote data processing systems. Thus the teaching of the current invention allows the setting up of modern Client/Server structures even if the actual BA has never been designed or prepared for this types of architectures.

10 Additional advantages of the invention provides for an integration of existing BAs into modern object-oriented (OO) environments becomes possible. The TMs may be generated as methods of object classes, called Transaction Object (TO) classes, which encapsulate the existing BAs.

15 Additional advantages of the invention provide that the integration of the BA into OO environment becomes seamless as also the TRs are generated as object structures. Furthermore being objects the TRs can now be enhanced by incorporating not only BA message descriptions but also by offering certain
20 processing capabilities leading to clear overall architectures.

A further objective of the invention provide for the detailed execution of TMs and their interplay with the BAs. Many of the benefits of this method have been discussed above.

3 Brief Description of the Drawings

25 **Figure 1** is a diagram reflecting the definition process of a Transaction Object Class and its associated Transaction Records building the User Interaction Graph.

Figure 2 is a diagram showing the parsing capability for analyzing IMS message definitions

Figure 3 is a diagram visualizing the overview of the individual data fields modelled in a Transaction Record together with the description of an individual data field within a Transaction Record

Figure 4 is a diagram visualizing the overview of the individual data fields modelled in a Transaction Record together with the description of an individual data field within a Transaction Record

Figure 5 is a diagram reflecting the process of modelling the activities for launching a transaction to process a next Transaction Record

Figure 6 is a diagram showing how to model the details of a transition of a first Transaction Record to a second Transaction Record

Figure 7 visualizes modelling details of an Entry Transition Record

Figure 8 offers an overview of a User Interaction Graph decomposition into TOMBuilders

Figure 9 is a diagram showing a first example of a User Interaction Graph and its decomposition into Transaction Object Methods

Figure 10 is a diagram showing a second example of a User Interaction Graph and its decomposition into Transaction Object Methods

Figure 11 is a diagram showing a third example of a User Interaction Graph and its decomposition into Transaction Object Methods

4 Description of the Preferred Embodiment

The present invention is part of a larger environment, called **VisualBridge**, allowing and guiding the integration and migration of Business Applications (BA) executed on a data processing system into modern environments. In particular the present invention relates to a method of providing access to BAs executed on a data processing system wherein said BAs hitherto offer their services interactively controlled by a multitude of BA panels and wherein said BAs may display succeeding BA panels dependent on user interactions, user specified data and the contents of any kind of data base the BA is operating on.

The illustrating embodiment of the invention is based upon BAs running under control of a Transaction Management System, in the current case the well-known **IMS** (Information Management System) of IBM corporation. BAs in terms of the invention are represented as real transactions in this environment. Another possibility could be BAs running under the also well-known **CICS** (Customer Information Control System) of IBM corporation.

Even if the current invention deals with BAs processed under IMS the invention by no means is limited to this type of BAs.

Actually any type of BA not just transactions in the sense of a transaction monitor are candidates for the current invention. The invention has been successfully implemented and verified within the Smalltalk based **VisualAge** product of IBM.

The goal of VisualBridge is the definition of object structures in the sense of object-oriented technology (OOT) encapsulating and wrapping existing BAs. The BAs themselves are wrapped into so-called **Transaction Objects (TO)** being enabled to autonomously controlling and executing the encapsulated BAs. **Business Objects (BOs)** on the other hand, being introduced as object structures modelling a unique entity or concept in terms of the underlying business, may exploit the TOs by transparently signalling the TOs to execute the encapsulated BAs. The subject of the current

invention extends the TOs by modelling, generating and executing
 OO methods, called **Transaction Methods (TM)** or, with an OO
 environment, **Transaction Object Methods (TOM)**, representing
 execution units of the underlying BAs. Each TOM is enabled to
 5 transparently and autonomously executing and controlling the BAs
 by handling a sequence of BA panels. Of course the original BA
 panels are not displayed by the TOMs though the BA is processing
 panel by panel not being aware of the fact that the panels are
 going to be intercepted and processed by the corresponding TOM.

10 In the following we will adapt, with respect to the term
 "object", to the language of OOT and, if unmisleadingly clear by
 the context, will refer to a class and the instance of a class in
 an unifying manner as object.

Further aspects of VisualBridge are:

- Modification of the underlying legacy application (IMS
 transactions in this case) should be limited to a minimum thus
 allowing a maximum of reuse of prior application development
 efforts.

Actually no modification of the legacy application is
 20 required at all.

- This migration architecture and environment therefore can be
 viewed as a mediator between the legacy code and the new object
 structure.

The new object structure on the other hand is the ideal
 25 basis

- for new types of graphical user interfaces (GUIs)
- as integration platform with additional applications
- IMS offers IBM's Advanced-Program-to-Program-Communication
 (APPC) protocol suite, a concrete protocol for communication
 30 purposes between programs across computer system boundaries. In
 addition APPC is available in IMS as a so-called
 "implicit-APPC" support allowing especially IMS transactions,

which originally have been developed for a 3270-type of terminal only, to be scheduled for execution transparently to the transaction from remote via APPC and to exchange data simulating a 3270-type terminal interaction based on the APPC protocol suite. The embodiment of the invention is based on the exploitation of that implicit APPC support.

- The transactions developed for a 3270-type terminal may also be controlled by handling and emulating the 3270 data stream directly. This would be a simple alternative to the implicit APPC approach above.

- BOs in the sense of the migration architecture are carriers of persistent data re-instantiated according user needs. Interaction with the BOs via the BO methods transparently will retrieve or modify BO data based on the existing interfaces of the remote transactions.

- An analysis of existing transaction applications will reveal that typically

- input/output data of a transaction is related not only to a single BO. Execution of a transaction thus could result in the transparent reference/instantiation of a multitude of BOs.

- a single transaction is related to a true subset of BO attributes only. This leads to the interesting effect that instantiation of the BOs may occur partially only, i.e. only with respect to a subset of BO attributes. BOs are made available only to the extend actually necessary. As desired the number of available BO attributes increases dynamically resulting in very effective and economic handling of storage resources.

- The migration architecture itself is to be implemented with OO-techniques.

Individual parts of the overall concepts are discussed as architectural elements below. By no means are the following

concepts limited to OO environments; they may be exploited for conventional, i.e. functional programming approaches as well.

4.1 The Overall Architecture

Of course the overall architecture itself is realized with a set of classes in the sense of an object-oriented programming language (in this case Smalltalk) offering a framework of classes with carefully adapted functionality.

Migration of an existing Online Transaction Processing Applications (OLTP) application to this proposed architecture means to implement a set of application specific classes by the process of sub-classing from the fundamental architecture base classes. At run-time instances of these application specific object classes will then support transparent execution of the existing OLTP transactions partially using BO attributes as OLTP data elements. The application specific classes implement that part of the overall functionality which is not generically available within the architectural base classes. This OO-type approach reduces the application-specific development effort significantly and at the same time increases the implementation flexibility.

Thus the client system offers a set of persistent BOs. Interactions with the BOs may transparently result in the execution of OLTP transactions completely hiding the underlying transaction system, the specific structure of transactions, the data bases manipulated by the transactions and of course the communication details of the client and the serving computer system running the OLTP application.

The major architectural elements to be discussed individually are:

1. Business Objects (BOs)
2. BO Instance Space (BOIS)
3. Transaction Records (TRs)

4. Transaction Objects (TOs)

4.1.1 Architectural Element: Business Objects (BOs) (Part 1)

BOs are key elements of the overall architecture as

- 5 • other architectural elements are accessible in an indirect manner only by interacting with the BOs
- the set of BO classes and BO instances form a layer shielding a BO exploiter from the rest of the migrated OLTP application and from the legacy application itself.

10 As indicated already by the name, BOs are the objects which in a straightforward sense are those entities the business domain is dealing with. With respect to nature and granularity the BOs are representing the model of the enterprise domain. Obvious BO examples are customers, contracts, orders, accounts, etc..

15 As BOs are carriers of persistent data to be retrieved and manipulated through the use of existing transactions, the BO's data spectrum is to be defined as the set of BO attributes. As an outstanding property the current approach of discovering and defining the BO attributes is characterized by the
20 peculiarity that it is based upon the input and output data spectrum of the existing transaction application, or in other words, it is based upon the existing **transaction's user interface (UI) specifications**. To understand the background and advantage of this methodology, it has to be realized

- 25 • that the UI specifications directly reflect the business related data, i.e. the data elements a business user of the transaction applications is dealing with. According to the experience with this type of approach based on this business point of view the data elements essential to the business
30 domain can be determined and related to the different types of BOs as BO attributes **easily** and very **efficiently**.
- that the existing transactions will be used in a later step for retrieval and manipulation of the BO data. The data being

part of the UI specification therefore exactly delimits the data spectrum available as BO attributes.

- that this avoids to analyze complicate data base structures grown historically in an evolutionary process. In addition the data bases themselves do not contain the business relevant data directly because certain types of mappings often occur between the data bases and user interface reflected data.

The data accessible through the transactions typically resides in (sometimes a multitude of) data bases. The BO **classes** therefore model various types of **persistent** BOs. To be able to uniquely identify the various instances of a BO of a single class the set of BO attributes has to distinguish

- BO **key attributes** (BOKA)

Typically they are represented by (a very small) subset of the BO attributes which, with respect to the underlying data bases, uniquely identify together with the BO class a certain BO instance. Of course the BO key attributes directly result from the key attributes of the corresponding data bases.

- BO **general attributes** (BOGA)

All the rest of the BO attributes, not allowing to uniquely distinguish the various BO instances within the data bases, are referred to as general attributes.

When relating the BO attributes with the UI specification of a multitude of existing transactions, following fundamental observations are of importance

- The input/output data elements in the UI specification of an existing transaction may refer to a **subset** of BO attributes. That is, with respect to a certain BO class only **part** of its attribute spectrum can be related to the input/output data elements of a single transaction. Conversely, there exist

further BO attributes which do not occur within the input/output data elements of a certain transaction.

- The input/output data elements in the UI specifications of an existing transaction may refer to subsets of attributes of different BOs.
- Different attributes of a certain BO may refer to input/output data elements of different transactions.

4.1.2 Architectural Element: BO Instance Space (BOIS)

Each instantiated BO is stored together with the other BOs within a specific collection, called the BO Instance Space (BOIS). As every BO is uniquely identified by the class of the BO together with the specific values of the BO key attributes this set of information also is sufficient for unique identification of BO instances within the BOIS.

The necessity of introduction of the concept of a BOIS is a direct consequence of the observations discussed in the chapter "Architectural Element: Business Objects (BOs) (Part 1)": if a single transaction typically delivers only parts of the spectrum of the attribute values of a BO instance and if thus the execution of multiple transactions is required to stepwise complete the BO attribute values, it must be possible

- to search for the possible existence of a certain BO instance at a unique place
- to stepwise complete/update the attribute values of a certain BO instance
- and at the same time to make the updated BO instance available to all exploiters of the BO.

This partial BO instantiation extended by the process of **stepwise completion** of BO attributes is called **materialization** in the following to distinguish it from a complete instantiation. This

concept of materialization offers some very attractive advantages:

- It allows for the operation with incomplete data.
- In contrast with other persistence models it offers very economical usage of storage. BO instances are not instantiated with respect to their whole attribute spectrum. This is of special importance as on the level of business relevance objects can become very large. BO instances are materialized only to the extend actually required by the exploiter.
- During lifetime of a BO instance its attribute spectrum may be completed step-by-step.

Directly correlated with the BOIS is the question of the lifetime of a certain BO instance. As in the general case a multitude of transaction executions might be required for a BO materialization, a BO instance must have a lifetime larger than that of an underlying materializing transaction. In the current solution a BO instance "lives", if not deleted explicitly by an exploiter, as long as at least one exploiter is referring to that BO instance.

4.1.3 Architectural Element: Transaction Records (TRs) (Part 1)

When calling a certain transaction it expects in the general case a certain amount of data as an input data block. As a result of the execution an output data block is returned. With respect to IMS these data blocks are called input/output areas (IOAREAs). Each of the IOAREAs may represent a panel displayed by the transaction on some computer screen.

From their inherent meaning the input/output data blocks can be viewed as a **message** known to the transaction which are exchanged for transaction invocation and return.

The various types of messages are modelled as specific object classes called Transaction Records (TRs). The important point about TRs is that they represent not an unstructured stream of bytes. TRs are equipped with descriptive information

- 5 • defining for each data element, being part of the message, the exact location, its length, its type, ...
- defining for each data element
 - the specific BO class
 - the specific BO attribute
- 10 it is representing
- defining the data elements not related to a certain BO class, but nevertheless represent input/output data of the transaction

Thus the TR architectures the central link between the BO classes and corresponding BO attributes on one side and the individual input/output parameters of a transaction. TRs therefore store mapping information from a data element within an input/output message onto a data element within a BO class, a BO attribute, and vice versa.

As already discussed together with the architectural element of a BO, different parameters of a message, i.e. different parameters of a TR, may be related with BO attributes of different BO classes.

This mapping information is of fundamental importance

- 25 • to support BO materialization
- Using the mapping information it is possible to store each parameter of an output message of a transaction into the correct BO attribute thus guiding the materialization process.
- to support the creation of an input message triggering the transaction execution

Based on the mapping information it is possible to create an input message processable by a certain transaction and to fill it

- with data resulting from well-defined BO attributes

- o with data from additional input parameters not related to a certain BO class

4.1.4 Architectural Element: Transaction Objects (TOs)

(Part 1)

- 5 Transaction Objects (TOs) are the classes to represent a model of at least one transaction. If a certain set of transactions is executed always in the same a predefined sequence, it may be reasonable to model such a group of transactions as a single TO.

10 Without restriction of generality let's assume for the further description that just a single existing transaction is encapsulated by a TO.

0042045 A TO class is the encapsulation of an existing transaction. When instantiated a TO is able to control and execute its corresponding transaction. At each point in time the TO is aware of the state of the encapsulated transaction.

20 To execute a certain transaction the TO is required to exchange messages with the transaction. Therefore all TRs, being a model and description of the transaction message, required for the message flow handling of this particular transaction are associated to the TO; i.e. the TO contains all messages which are of importance when communicating with the specific transaction. Of course it is not required to display the messages on a computer screen, much more the messages and their contents are intercepted and made available as objects in form of TRs.

- 25 As a transaction may be processed on a remote data processing system a certain amount of definitions, called connection specifications, are incorporated into the TO allowing a TO instance to set up a communication connection to the possibly

remote transaction system. The connection specifications encompass data like

- the address of the remote computer system
- the specific transaction (on the remote system) to be started
- authorization related data like userid and password
- the concrete communication protocol to be used
- etc.

4.1.5 Transaction Steps and Problem-Specific TO Methods (TOMs) (Part 1)

Only in rare circumstances execution of a transaction is the result of a single message exchange of a requesting and an answering message with the transaction being completed afterwards. In most cases a possibly lengthy sequence of message exchanges, i.e. exchange of panel screens, occur from the start to the completion of a transaction. Generally such types of transactions are named **conversational transactions** for obvious reasons.

Typically a sequence of message exchanges representing a single transaction can be decomposed in a sequence of **transaction steps**. Each transaction step starts with a message containing information specified by a user, is followed by receiving and sending further messages which could be processed automatically, ending with (but including) a message to be sent to the transaction which again requires information by a user. Thus transaction steps are a decomposition of conversational transaction execution into units of message sequences which can be executed automatically without human intervention.

Each of these transaction steps is modelled as an individual instance method of the TO called **Transaction Object Method (TOM)**.

Two types of parameters could be part of a TOM invocation

- key attributes uniquely identifying BO instances

If for setting up the message to be sent to the transaction, data is required belonging to BOs, then only the key attributes identifying the BOs are to be specified. As described below generic TO logic is able to retrieve the required BO attribute data for setting up the input message to the transaction.

- additional TOM method parameters

This type of parameter is required only if the parameter does not represent an attribute of some BO.

When being called, a TOM triggers to send a message to the (remote) transaction. As the TOM executes a certain transaction step it knows the identity of the messages, i.e. the TRs (refer to the chapter "Architectural Element: Transaction Records (TRs) (Part 1)" for more information) which have to be prepared and sent to the transaction. The TOM issues this processing by calling an architected instance method ***inXaction*** of that TR instance responsible for setting up the particular message.

4.1.6 Architectural Element: Transaction Records (TRs) (Part 2)

Besides the more static and descriptive aspects as depicted in the chapter "Architectural Element: Transaction Records (TRs) (Part 1)" TRs encompass also certain dynamical characteristics realized within architected methods.

These activities are performed in concert with the specific TO instance related to the TR instance. In endorsement to the description of the architectural element of a TO (refer to the chapter "Architectural Element: Transaction Objects (TOs) (Part 1)") it has to be stressed that

- each TR is instantiated together with its related TO instance with which it sets up a one-to-one correspondence
- each TR instance knows its related TO instance

The dynamical characteristics are two-fold and are realized within the following two architectural methods.

4.1.6.1 The Architected Instance Method *inXaction*

- 5 The TR instance method *inXaction* is responsible for
- creating the correct message template to be transmitted to the transaction

Which message object has to be created results from the nature of the current TO instance, as each TR is responsible for handling a specific message.

- copying all required information into the TR; i.e. into the message

As outlined in the discussion on TRs in chapter "Architectural Element: Transaction Objects (TOs) (Part 1)" a TR stores descriptive information for the individual data elements of the TR.

Those TR elements which represent BO attributes can be filled in using the BO key attributes being part of the TOM invocation. The BO key attributes allow the method *inXaction* to locate the BO instance within the BOIS and to retrieve the required BO attribute values.

Those TR elements not related to BO attributes are expected to be parameters specified as part of the TOM invocation thus permitting the *inXaction* method to gather this data too.

- transmitting the message to the remote transaction
- passing the processing of the transaction's output message over to the architectural instance method *outXaction* of the responsible TR instance for further processing.

The responsible TR instance can be determined by analyzing the received TR.

4.1.6.2 The Architected Instance Method *outXaction*

outXaction is responsible for analyzing and processing the output message by

- materializing all BOs affected by the TR contents
- 5 As outlined in the discussion on TRs in the chapter "Architectural Element: Transaction Objects (TOs) (Part 1)" the TR stores the descriptive information for the individual data elements of the TR. Thus *outXaction* can
 - determine the TR elements which represent BO attributes
 - 10 ○ locate the affected BOs in the BO Instance Space BOIS or create the BO instance if not existent yet
 - copy the BO attribute data from the TR elements to the BO itself
- returning the list of materialized BOs to its caller

15 4.1.6.3 The Architected Instance Method *inXaction* (Part 2)

- *inXaction* returns to its caller the list of materialized BOs received upon return from *outXaction*.

4.1.7 Transaction Steps and Problem-Specific TO Methods (TOMs) (Part 2)

20 Upon return from the invocation of *inXaction* the TOM receives the list of materialized BOs.

The TOM has to decide, based upon the output message, i.e. the TR received from the transaction, how to proceed.

25 If the transaction step has been completed simply the list of materialized BOs is passed to its caller. The TOM triggers to send the next message to the remote transaction by issuing *inXaction* again with respect to that TR instance responsible for

handling the next message and repeating the sequence of activity
inXaction-outXaction once more.

4.1.8 Architectural TO Features and Class-Hierarchy

To reduce the amount of implementation effort for each TO class
 5 modelling an existing transaction all the generic, i.e.
 architectural TO features, are realized within the TO super-class
BplTransObj. As depending on the type of transaction monitor
 executing a certain transaction the handling of the message flow
 between the TO and the remote transaction **might** be slightly
 10 different sub-classes may have been introduced for the individual
 supported transaction monitors like IMS, CICS, The
 sub-class *BplIMSTransObj*, *BplCICSTransObj*, ... might implement
 the corresponding transaction monitor related deviations. If such
 deviations do not exist these intermediate classes can be
 15 omitted.

The class structure delivers the spectrum of architectural TO
 features like

- communication handling
- transaction invocation and message exchange
- 20 • BO materialization

to the problem specific TO classes which are subclasses thereof.

The remaining implementation effort within the problem specific
 TO classes representing the migrated transactions is limited to

- choosing the concrete communication model and defining the
 25 communication specifications
- modelling the TRs the TO class is responsive to
- realizing the concrete TOMs implementing the corresponding
 transaction steps

TOM implementation could mean to associate a state to a TO
 30 instance which checks the sequence of TOM executions if the

remote transaction does not allow TOM execution independent of the TOM predecessor.

4.1.9 Architectural Element: Business Objects (BOs) (Part 2)

As mentioned above, the BOs may exploit the TOs by transparently signalling the TOs to execute the encapsulated transactions. Those methods of a BO which result in the execution of a (or part of a) transaction are called **Business Object Methods (BOMs)**. The problem specific BOMs are the only interface to exploiters for the overall architecture to transparently execute, without knowledge of the underlying architecture, remote transactions.

Two types of parameters could be part of a BOM invocation

- key attributes, uniquely identifying other BO instances (apart of that BO the BOM belongs to)
- additional BOM method parameters

This type of parameter is required only if a parameter does not represent an attribute of some BO.

The BOMs actually will call one or several TOMs for corresponding transaction execution. On return the BOM passes to its caller the list of materialized BOs as received from the executed TOMs. The application programmer is free to combine any TOM sequence within a BOM.

4.2 Defining Transaction Objects (TOs) and Transaction Object Methods (TOMs)

As TOMs are methods of TO classes the definition and generation process of the TOMs is part of the definition and generation process of the TOs. A specific development environment of VisualBridge, called the VisualBridge Graph Editor (VBGE) guides and supports the development process in a graphical manner. The VBGE is based upon VisualAge's Composition Editor.

The definition and generation process may be further supported by VisualBridge parsers. VisualBridge parsers automate the whole process further by being able to read, parse and transform the message definitions of the messages processed by the transaction.

- 5 This is possible as in the most (transaction) execution environments the panels, i.e. the user interfaces, of an application are defined by some kind of descriptive language. Thus most of the information on the individual panel elements may be extracted from these user interface specifications. In case of
- 10 the IMS execution environment the panel and message definitions are available as so-called Message Input Descriptor/Message Output Descriptor (MID/MOD) definitions.

The method process to define and generate the TOs with the corresponding TOMs encompass the following individual steps:

1. Definition of a TO as an encapsulation of a transaction
2. Modelling each individual message processed by the encapsulated transaction
3. Definition of the activities for each current message launching the transaction to process a next message, i.e. to perform a message transition
4. Definition of the sequence of messages as processed by the transaction and modelling this sequence as a directed graph, called User Interaction Graph (UIG)
5. Selecting the specific activity required to launch the transaction to process after a current message a next message
6. Classifying the TRs as Entry TR, External TR, Interactive TR or Preemptive TR
7. Generating a message description for each modeled message as TR
8. Connecting a TO to a transaction system
9. Generating the TOMs

The sequence of the above steps is not as fixed as it might look at the first sight. First of all, the whole process is a repetitive one, i.e. it may be repeated beginning at each arbitrary step. Second, the classification step of the TR may be performed as soon as the a model of a message has been introduced. Third, the generation of the message description may be not a separate step but a continuous process. Each change of the modeled messages may automatically update the message description, i.e. the TR.

4.2.1 Definition of a TO

The definition of a TO is done within the VisualAge development environment by subclassing from the class *BplTransObj*. Each TO is a non-visual composite part in the sense of VisualAge. Such a part is created from VisualAge's Application Browser window. This creation automatically starts the VisualAge Composition Editor which is the heart of the Transaction Object development. Within the Composition Editor the TO is visually constructed. Within Fig.1 the nonvisual TO is symbolized by the background 100.

4.2.2 Modelling the Individual Transaction Messages

To model a certain transaction messages first a skeleton for a TR is created by dragging in Fig. 1 a TR skeleton from the palette 108 to the background 100. Within Fig. 1 the TRs 101 to 103 are examples of this process.

To speed up the process of modelling the message details the message definitions available from within the IMS execution environment may be parsed. This parser is accessible from the settings view of any TR. Fig. 2 shows the "Parser" page of the settings view with the capability to search for a file storing the IMS message definitions and to parse its

contents. The parser allows to get all the structural information of an transaction message out of the corresponding screen map definition, i.e. MFS for IMS/DC or BMS for CICS. In cases where the underlying transaction system allows to send back only a subset of the sent data, it is possible to parse both map definitions, e.g. MOD and MID definitions of MFS.

The "Edit" page of the settings view visualized in Fig. 3 and 4 enables to change the parsed information from the MIDs and MODs or build up that structural information manually. Fig. 3 and 4 are actually a snapshot of the same window too large to fit on the the screen. Further message elements may be added 302 or deleted 303. The parsed or manually created message elements are registered in the list 301. Every individual message element, for instance 304 may be changed. Fig. 4 shows the details of the element 304 which may be edited. As Fig. 4 depicts, each element is characterized by its length 401, its offset 402, alignment 403 and so forth.

4.2.3 Definition of Activities for each TR

The definition step of the activities for each current TR launching the transaction to process a next TR, i.e. to perform a message transition, is available from the "Action" page of the settings view, refer to Fig. 5. The first combobox named "Actions for Record" 501 contains all actions already defined for this TR. To remove an action select it here and press the "Delete Action" button 502. The combobox 503 contains all possible actions. To add an action a Program Function (PF) key is to be selected here and to be added by 504 to the list 501.

4.2.4 Definition of the Message Sequence Processed by the Transaction

To model for a TO the sequence in which the encapsulated transaction processes the messages edges (arcs) are to be drawn between the TRs associated to that TO exactly in the way they follow each other in the interaction flow. Those edges are

- 5 implemented as Event-to-Action connections in the sense of VisualAge. There connections between 2 TRs are drawn by:
 1. moving the mouse pointer to the first TR being the source of the connection and select **connect** from its pop-up menu.
 2. from the appearing menu selecting the event **nextRecord**.
 - 10 3. moving the mouse over the second TR being the target of the connection and select **outXaction** from its pop-up menu.

After this definition process a connection line is drawn between the two TRs signifying the message processing sequence of the transaction and making the target TR sensitive to a **nextRecord** event.

The definition process introduces the following behavior to the TRs:

1. Whenever the method **inXaction** for the source TR is invoked explicitly or implicitly what happens is that the source TR sends its data to the encapsulated transaction and waits for an response.
2. When the response arrives the source TR asks its TR successors, which one is responsible for its processing by sending the event **nextRecord**.
- 25 3. This event triggers the action **outXaction** of the correct successors TRs, i.e. the target TRs. The correct target TR responsible for the response will start processing the TR's contents.
- 30 4. After that the target TR implicitly invokes **inXaction** on itself, resulting in proceeding with the next processing entity.

The result of this modelling step is the UIG for currently modelled TO. Fig. 1 gives an example of an UIG. Within Fig.1 the edges 110 to 112 describe and visualize the sequence of message processing.

5 4.2.5 Selecting the Specific Activity for Message Transition

Within this step it has to be defined for a the current message model, i.e. for a TR, by which kind of specific activity taking place with respect to the current TR the encapsulated transaction is launched to sent the specific successor message, i.e. a successing TR. Fig. 6 visualizes the "Transition" page of the settings view of a TR for which the activity for a message, i.e. TR transition is to be defined. Actually Fig. 6 is snapshot of one window too large to fit on the the screen. All possible TR successors are listed in the combobox 601. Its contents is in accordance to the UIG defined in the previous steps, i.e. its contents consists of all TR connect with the current by an edge of the UIG.

For every individual successor TR the set of parameters and its values (if special constants are passed) together with an action (a PF key for instance) by which this node can be reached has to be modelled. The default behavior is that every successor needs all parameters without special values together with the ENTER key as default action.

For the selected TR successor 601 the parameters listed in the "Parameter" combobox 602 (representing message or panel elements of the successing message) can be added or changed by pressing "Add to Succ" 607. If the "Constant" text field 603 is filled with a certain value the added parameter will be associated with this constant. This defines that the selected successor will be reached by passing the specified constant for that parameter in the message represented by the current TR to the transaction for

processing. If no constant value is added any value must be possible to reach the specified successor TR. All parameter associations added to launch the encapsulated transaction to send the successor message once the current message is processed are listed in the combobox 602 labeled "Parameters for the Selected Successor".

An action can be specified in addition which, together with the above parameter values, triggers the encapsulated transaction to launch the successor TR. This action is selected from the combobox 604 named "Action". If a successor TR may be reached with more than one action (for example PF1 and ENTER) one of them must be chosen. This action will then be used by the generation process for the TOMs.

The so-called Transition Groups can be listed by pressing "View" 606. A Transition Group contains all successor TRs reachable by the same parameter constellation from the current TR. Each Transition Group will result in a separate TOM (refer also to the description below).

4.2.6 Classifying the TRs

TRs may be of different types, i.e. they may incorporate various indications designating their specific nature. Though the current description illuminates the step of classifying the TRs at a precise location within the overall methodology it has to be pointed out that classification of the TRs may take place at any point in time after defining a TR within the VBGE.

Currently the following TR types can be distinguished:

- **Entry TR**

An Entry TR is an encapsulation and model of a message to be exchanged with the transaction execution environment (IMS in our case) by which a certain transaction is started. Consequently an Entry TR encompasses at least the IMS

transaction code of the transaction to be started. In addition all further input message elements have to be modelled within an Entry TR required by the transaction to send its first output message as a result. Therefore apart from the transaction code being part of an Entry TR there is no difference to an Interactive TR as outlined below.

A model of an Entry TR is visualized in Fig. 7 showing the "Edit" page of the settings view of an Entry TR. 701 indicates the important and specific data element in that Entry TR, the transaction code required to start the transaction. Of course an additional number of parameters, like 702, may be modelled.

○ **External TR**

An External TR is an encapsulation and model of a message handled by another TO, i.e. an External TR is part of the UIG of another TO outside the scope of that TO currently modelled with VBGE. It thus provides the mechanism to model existing transactions calling each other, whereby the transactions are encapsulated and handled by different TOs. The concept of External TRs supports the reuse of transaction encapsulated and modelled by other TOs already.

That at TR is an External TR may be specified on a page of the settings view of the TR within the VBGE together with the specific TO the External TR refers to. An External TR is symbolized with a specific identifying icon within the UIG.

○ **Interactive TR or Preemptive TR**

Interactive or Preemptive distinguish whether input values for a message encapsulated by a TR can be provided in advance. If input for a TR can be provided in advance a TR is called and indicated Preemptive, which is also reflected by the color of the TR icon within the UIG. In other words a Preemptive TR is part of an execution unit of succeeding messages within a UIG and thus indicates a message to be processed automatically by a TOM to be generated later. If

input could not be provided in advance for a TR it is called Interactive, which is also reflected by the color of the TR icon within the UIG. In other words an Interactive TR indicates a TR being the first message of an execution unit of messages and thus starts the message exchange of a certain TOM to be generated later. In general when creating a TR within the VBGE it is first assumed that the TR is an Interactive TR. It is the up to the user to modify this classification. Within the "Type" page of a TR's setting view a button allows to toggle between a Preemptive or Interactive indication of a TR.

4.2.7 Generating the Modelled TRs

The modelled TRs may be either generated continuously after each modification occurring during the editing session within the VBGE. An other alternative is to generate the TRs on user request by allowing a user within the VBGE to explicitly start the generation process. A next alternative is to start the TR generation process when the VBGE is closed.

4.2.8 Connecting a TO to a Transaction System

To identify the specific transaction environment capable of executing the specific transaction encapsulated by a certain TO that TO has to be "connected" to the transaction environment. With the same definition process the specific transaction environment as well as the specific network protocol to communicate with the transaction execution environment is designated. This offers complete freedom and transparency whether the TO and the encapsulated transaction are executed on the same or on remote data processing systems.

This process of "connecting a TO to a transaction system" is performed by dragging a "connection specification part" skeleton, symbolized by an icon within the parts palette 108, to the

background 100. Now having the connection part available an attribute-to-attribute connection between the connection part's **self** attribute and the **ConnectionSpec** attribute of the TO completes the first part of the definition process. Currently the following connections to transaction systems are supported:

- IMS implicit APPC
- CICS
- Emulation of the 3270 data stream

The second part of the definition process is achieved by entering information within the settings view of the connection specification part. Via this notebook all aspects to establish communication with the transaction system must be defined. For instance address of the potentially remote data processing system, userid, password, and so forth. 104, 105 and 106 is the result of this definition process.

4.2.9 Generating the TOMs

Actually a TOM starts or continues a transaction and works through a certain subgraph within the UIG. Before generating the TOMs making up the complete UIG all modelling and definition steps above have to be completed carefully. Especially the categorization of TRs into Interactive or Preemptive TRs has to be completed as this categorization defines where within the UIG a new TOM begins and where it ends.

Messages encapsulated as TRs and exchanged with the encapsulated transaction which contain data elements which typically cannot be provided in advance typically will be classified as Interactive TRs. Those TR encapsulating for instance output information only and/or requesting input information which can be provided in advance typically will be classified as preemptive TRs.

With respect to the TOM generation process and from the TOM point of view a TR of the Interactive type is the end point of a first TOM and the starting point of the next TOM. All data elements of

a Preemptive TR which are of input character will be reflected as input parameters of the TOM to be generated. The same statement holds for the Interactive TRs too. Input fields of a TR which are set to a fixed value or are related to a BO attribute are not reflected in a TOM interface as parameter. Output fields in a TR will be made available with their current values from a result object which will be returned by the TOM. As a remark, when talking here about TR input/output fields only those are of interest, which have no association with a BOA. Data fields of a TR having an association with a BOA are mapped automatically and are not passed via the TOM interface; i. e. these input fields are retrieved from the associated BO instances directly and written to the message encapsulated by the TR while these output fields are written to the associated BOA thus making up a part of the partial materialization process mentioned above. Without a materialization process of course also the BOAs would have to be interface parameters of a generated TOM.

For the TOM concept also the notion of a Transition Group is of importance. When a certain message encapsulated by a TR is sent to the transaction for processing it is not known in advance in all cases which message will be returned by the transaction as response (this may depend on the data the transaction is operating on). Therefore all successor TRs in the sense of the UIG potentially reachable from a current TR with the same parameter values as defined in the steps above represent a Transition Group and will be incorporated to in the same TOM. On the other hand different Transition Groups are established if different parameter values are required to launch the transaction to sent the corresponding messages. Different parameter values might mean that different constants for one or more input values or a different combination of input fields are defined for triggering TR transitions.

As a first activity to generate the TOMs the settings view of the definition environment of the TO (refer to Fig. 1) offers an action "create TOMBuilder". Whenever this activity is started first all available TOMs, potentially generated in a previous "create TOMBuilder" step are removed. Then the whole UIG is traversed and analyzed including all definitions and specifications delineated within the VBGE. For every TOM which could theoretically be built from this graph a so-called "TOMBuilder" object is created. A TOMBuilder object is not the TOM itself but it stores all required information allowing the TOMBuilder object when executed to generate the TOM it is representing. A separate TOM will be generated for each subgraph in the UIG of the modelled TO starting with an Entry TR or an Interactive TR including all succeeding Preemptive TRs up to the next Interactive TR or to the final Preemptive TR in the UIG or up to an External TR.

As depicted in Fig. 8 within the settings view of the TO modelled in the VBGE the UIG, decomposed into a TOM graph 801 (represented in a Smalltalk notation), is visualized. In the list 802 each of generated TOMBuilder may be executed 803 to actually generate its corresponding TOM.

To further improve the understanding of the TOM generation process a set of UIG scenarios should be discussed explaining the TOM decomposition process.

Fig. 9 shows a UIG consisting of a linear chain of one Interactive TR 901 and 3 Preemptive TRs 902 to 904. According above mentioned TOM generation rules only one TOM 905 will be generated consisting of the execution 901 to 904 of TRs.

Fig. 10 shows a more complex UIG consisting of a single Interactive TR 1001 and Preemptive TRs 1002 to 1006. Assuming that the execution unit of TR 1001, 1002, 1003 requires a different parameter constellation than the rest of the UIG then according above mentioned TOM generation rules 2 different TOMs

will be generated. A first TOM 1008 consisting in the UIG sub-graph of TRs 1001, 1002 1004, 1005, 1006 and a second TOM consisting in the sub-graph of TRs 1001 to 1003.

Fig. 11 depicts an even more intricate UIG made up of Interactive TRs 1101 and 1103, made up of Preemptive TRs 1102, 1105, 1106 and made up of External TRs 1104, 1107. The UIG decomposition process will thus generate 3 TOMs.

- A first TOM 1110 starting with the Interactive TR 1101 ending with the External TR 1107 and thus consisting of the execution of TRs 1101, 1102, 1105, 1106 and 1107.

- A second TOM 1108 starting with the Interactive TR 1101, also containing Preemptive TR 1102 and ending with the next Interactive TR 1103.

- A third TOM 1109 starting with the Interactive TR 1103 and ending with the External TR 1104.

5 Acronyms

BA	Business Application
BOA	Business Object Attribute
BOGA	Business Object General Attributes
BOIS	Business Object Instance Space
BOKA	Business Object Key Attribute
BOM	Business Object Method
CICS	Customer Information Control System
IMS	Information Management System
MFS	Message Format Service
MID	Message Input Descriptor
MOD	Message Output Descriptor
OLTP	Online Transaction Processing
OO	Object Orientation
OOT	Object Oriented Technology

	TO	Transaction Object
	TOM	Transaction Object Method
	TM	Transaction Method
	TR	Transaction Record
5	TST	Transaction Step
	UIG	User Interaction Graph
	VBGE	VisualBridge Graph Editor

What is claimed is:

1 1. A method executable by a computer of automatically
2 generating access to at least one Business Application executed
3 on a data processing system, wherein said Business Application
4 is panel-driven and offers its services interacting with a user
5 controlled by at least one Business Application panel and
6 wherein said Business Application processes succeeding Business
7 Application panels dependent on user interactions or user
8 specified data or the contents of any kind of data base the
9 Business Application is operating on, said computerized method
10 comprising:

11 an analysis step of analyzing a description of said
12 Business Application panels determining their input data and
13 a generation step generating according to said analysis
14 step at least one procedure, called Transaction Method, said
15 Transaction Method being callable from a program and said
16 Transaction Method being generated to autonomously executing at
17 least a part of said Business Application without interacting
18 with said user;

19 wherein said generation step generates program code into
20 said procedure, which, when executed, is providing required
21 input data according to said analysis step to at least one
22 sequence of succeeding Business Application panels, said
23 sequence comprising at least one Business Application panel, and

24 wherein said generation step generates program code into
25 said procedure, which, when executed, is performing a required
26 activity for launching said Business Application to autonomously
27 process said at least one sequence of succeeding Business
28 Application panels without interaction with said user.

1 2. The method according to Claim 1 further comprising
2 generating said description of said Business Application panels
3 prior to said analysis step wherein said Business Application

panel description being independent from the system environment in which said Business Application is implemented and wherein the method encompasses:

a Business Application panel modelling step, in which at least one of said Business Application panels, processed by said Business Application as input or output panels, called Business Application messages, is modelled with respect to individual Business Application panel elements;

a Business Application message description generation step, in which at least one of said Business Application panels, processed by said Business Application as input or output panels, called Business Application messages, is parsed with respect to individual Business Application panel elements; and

in which for each modelled Business Application message Transaction Record is generated storing said Business Application message description;

a User Interaction Graph generation step, in which the sequence of Business Application messages as processed by said Business Application is stored in at least one directed User Interaction Graph.

3. The method according to Claim 2 further comprising:

a Business Application message transition generation step in which a Business Application message transition action is generated to launch the Business Application to process a next Business Application panel after a current Business Application panel according to the sequence within the User Interaction Graph; and

in which said Business Application message transition action is stored within the generated Transaction Record during said Business Application message description generation step.

4. The method according to Claim 2 wherein said Business Application message description generation step stores

3 descriptive information on the individual panel elements
4 assembling said Business Application message with respect to
5 type or length or position or indications which of the panel
6 elements represent input and/or output elements within said
7 Transaction Record.

1 5. The method according to Claim 2 wherein said Business
2 Application panel description is generated by parsing and
3 analyzing Business Application message implementations of the
4 system environment said Business Application is implemented by
5 interactions with a user of the data processing system gathering
6 required Business Application panel description information.

0046601 6. The method according to Claim 2 wherein said Business
0046602 Application message description generation step incorporates
0046603 indications on specific characteristics into the generated
0046604 Transaction Record encompassing
0046605 an Entry Transaction Record indication, characterizing a
0046606 Business Application messages required for an initial start of a
0046607 Business Application execution;
0046608 an External Transaction Record indication, characterizing a
0046609 Business Application message being part of a second User
0046610 Interaction Graph and thus describing a Business Application
11 message sequence with a branch from a first User Interaction
12 Graph to said second User Interaction Graph;
13 an interactive Transaction Record indication, indicating a
14 Business Application message representing a first Business
15 Application message of an execution unit of succeeding Business
16 Application messages within said User Interaction Graph
17 encompassing at least said interactive Transaction Record; and
18 a preemptive Transaction Record indication, indicating a
19 Business Application message being part of said execution unit
20 of succeeding Business Application messages and not being a
21 first Business Application message in said execution unit.

1 7. The method according to Claim 6 in which at least one
2 Transaction Method is generated and provided to execute an
3 execution unit of succeeding Business Application messages,
4 said Transaction Method is starting said execution of
5 Business Application messages with an interactive Transaction
6 Record;
7 said Transaction Method is proceeding said execution of
8 Business Application messages with all preemptive Transaction
9 Records succeeding said interactive Transaction Record within
10 the User Interaction Graph;
11 said Transaction Method is ending said execution of
12 Business Application messages with a next interactive
13 Transaction Record or with a last preemptive Transaction Record,
14 if no Transaction Record is succeeding said last preemptive
15 Transaction Record within the User Interaction Graph.

1 8. The method according to Claims 7 wherein said generated
2 Transaction Method
3 encompasses as Transaction Method input parameters all
4 input elements of all Business Application messages modelled by
5 Transaction Records belonging to said execution unit and
6 encompasses as Transaction Method output parameters, all
7 output elements of all Business Application messages modelled by
8 Transaction Records belonging to said execution unit.

1 9. The method according to Claim 1 extending the generated
2 Transaction Method by communication relevant capabilities
3 provided for
4 allowing the Transaction Method to be executed in a local
5 data processing system and
6 allowing the Transaction Method to communicate with a
7 remote data processing system via a computer network using
8 anyone of the available communication protocols and

9 allowing the Transaction Method to control execution of
10 said underlying Business Application on said remote data
11 processing system.

1 10. The method according to claim 1 in which the Transaction
2 Method is generated as a method of a Transaction Object (TO)
3 class in the sense of object-oriented technology for
4 encapsulating and controlling said Business Application and said
5 Transaction Method method is being called TO Method (TOM).

1 11. The method according claim 1 in which said Transaction
2 Record is generated as Transaction Record class in the sense of
3 object-oriented technology.

1 12. In a computer automatically generating access to at least
2 one Business Application executed on a data processing system,
3 wherein said Business Application is panel-driven and offers its
4 services interacting with a user controlled by at least one
5 Business Application panel and wherein said Business Application
6 processes succeeding Business Application panels dependent on
7 user interactions or user specified data or the contents of any
8 kind of data base the Business Application is operating on, an
9 apparatus comprising:

10 means for analyzing a description of said Business
11 Application panels determining their input data and

12 means for generating at least one Transaction Method
13 according to said analysis, said Transaction Method being
14 callable from a program and said Transaction Method being
15 generated to autonomously execute at least a part of said
16 Business Application without interacting with said user;

17 wherein said means for generating includes program code in
18 said procedure, which, when executed, is providing required
19 input data according to analysis by said means for analysis to

20 at least one sequence of succeeding Business Application panels,
21 said sequence comprising at least one Business Application
22 panel, and

23 wherein said means for generating includes program code in
24 said procedure, which, when executed, is performing a required
25 activity for launching said Business Application to autonomously
26 process said at least one sequence of succeeding Business
27 Application panels without interaction with said user.

1 13. The apparatus according to Claim 12 wherein said means for
2 generating generates a Business Application panel description of
3 said Business Application panels prior to analysis by said means
4 for analysing wherein said Business Application panel
5 description being independent from the system environment in
6 which said Business Application is implemented and wherein the
7 apparatus includes:

8 a Business Application panel modelling means in which at
9 least one of said Business Application panels, processed by said
10 Business Application as input or output panels, is modelled into
11 Business Application messages with respect to individual
12 Business Application panel elements;

13 a Business Application message description generation means
14 in which at least one of said Business Application panels,
15 processed by said Business Application as input or output
16 panels, is parsed into Business Application messages with
17 respect to individual Business Application panel elements; and

18 in which for each modelled Business Application message, a
19 Transaction Record is generated storing a Business Application
20 message description; and

21 a User Interaction Graph generation means, in which a
22 sequence of processed Business Application messages is stored in
23 at least one directed User Interaction Graph.

1 14. The apparatus according to Claim 13 wherein said apparatus
2 further encompasses:
3 a Business Application message transition generation means,
4 in which a Business Application message transition action is
5 generated to launch the Business Application to process a next
6 Business Application panel after a current Business Application
7 panel according to the sequence within the User Interaction
8 Graph; and
9 in which said Business Application message transition
10 action is stored within the generated Transaction Record by said
11 Business Application message description generation means.

1 15. The apparatus according to Claim 13 wherein said Business
2 Application message description generation means stores
3 descriptive information on the individual panel elements
4 assembling said Business Application message with respect to
5 type or length or position or indications which of the panel
6 elements represent input and/or output elements within said
7 Transaction Record.

1 16. The apparatus according to Claim 13 wherein said Business
2 Application panel description is generated by parsing and
3 analyzing Business Application message implementations of the
4 system environment, said Business Application being implemented
5 by interactions with a user of the data processing system
6 gathering required Business Application panel description
7 information.

1 17. The apparatus according to Claim 13 wherein said Business
2 Application message description generation means incorporates
3 indications on specific characteristics into the generated
4 Transaction Record encompassing:

5 an Entry Transaction Record indication, characterizing a
6 Business Application messages required for an initial start of a
7 Business Application execution;

8 an External Transaction Record indication, characterizing a
9 Business Application message being part of a second User
10 Interaction Graph and thus describing a Business Application
11 message sequence with a branch from a first User Interaction
12 Graph to said second User Interaction Graph;

13 an interactive Transaction Record indication, indicating a
14 Business Application message representing a first Business
15 Application message of an execution unit of succeeding Business
16 Application messages within said User Interaction Graph
17 encompassing at least said interactive Transaction Record; and

18 a preemptive Transaction Record indication, indicating a
19 Business Application message being part of said execution unit
20 of succeeding Business Application messages and not being a
21 first Business Application message in said execution unit.

1 18. The apparatus according to Claim 17 in which at least one
2 Transaction Method is generated and provided to execute an
3 execution unit of succeeding Business Application messages,

4 said Transaction Method is starting said execution of
5 Business Application messages with an interactive Transaction
6 Record;

7 said Transaction Method is proceeding said execution of
8 Business Application messages with all preemptive Transaction
9 Records succeeding said interactive Transaction Record within
10 the User Interaction Graph;

11 said Transaction Method is ending said execution of
12 Business Application messages with a next interactive
13 Transaction Record or with a last preemptive Transaction Record
14 if no Transaction Record is succeeding said last preemptive
15 Transaction Record within the User Interaction Graph.

1 19. The apparatus according to Claims 18 wherein said generated
2 Transaction Method:

3 encompasses as Transaction Method input parameters, all
4 input elements of all Business Application messages modelled by
5 Transaction Records belonging to said execution unit; and
6 encompasses as Transaction Method output parameters, all
7 output elements of all Business Application messages modelled by
8 Transaction Records belonging to said execution unit.

1 20. The apparatus according to Claim 12 extending the generated
2 Transaction Method by communication relevant capabilities
3 provided for

4 allowing the Transaction Method to be executed in a local
5 data processing system and

6 allowing the Transaction Method to communicate with a
7 remote data processing system via a computer network using
8 anyone of the available communication protocols and

9 allowing the Transaction Method to control execution of
10 said underlying Business Application on said remote data
11 processing system.

1 21. The apparatus according to claim 12 in which the
2 Transaction Method is generated as a Transaction Object class of
3 object-oriented technology for encapsulating and controlling
4 said Business Application.

1 22. The apparatus according claim 12 in which said Transaction
2 Record is generated as a Transaction Record class of
3 object-oriented technology.

1 23. A program storage device readable by a machine tangibly
2 embodying at least one program of instructions executable by the
3 machine to perform a method of automatically generating access

4 to at least one Business Application executed on a data
5 processing system, wherein said Business Application is
6 panel-driven and offers its services interacting with a user
7 controlled by at least one Business Application panel and
8 wherein said Business Application processes succeeding Business
9 Application panels dependent on user interactions or user
10 specified data or the contents of any kind of data base the
11 Business Application is operating on, said method comprising:

12 an analysis step of analyzing a description of said
13 Business Application panels determining their input data and
14 a generation step generating according to said analysis
15 step at least one procedure, called Transaction Method, said
16 Transaction Method being callable from a program and said
17 Transaction Method being generated to autonomously executing at
18 least a part of said Business Application without interacting
19 with said user;

20 wherein said generation step generates program code into
21 said procedure, which, when executed, is providing required
22 input data according to said analysis step to at least one
23 sequence of succeeding Business Application panels, said
24 sequence comprising at least one Business Application panel, and

25 wherein said generation step generates program code into
26 said procedure, which, when executed, is performing a required
27 activity for launching said Business Application to autonomously
28 process said at least one sequence of succeeding Business
29 Application panels without interaction with said user.

1 24. The program storage device according to Claim 23 further
2 comprising generating said description of said Business
3 Application panels prior to said analysis step wherein said
4 Business Application panel description being independent from
5 the system environment in which said Business Application is
6 implemented and wherein the method encompasses:

7 a Business Application panel modelling step, in which at
8 least one of said Business Application panels, processed by said
9 Business Application as input or output panels, called Business
10 Application messages, is modelled with respect to individual
11 Business Application panel elements;

12 a Business Application message description generation step,
13 in which at least one of said Business Application panels,
14 processed by said Business Application as input or output
15 panels, called Business Application messages, is parsed with
16 respect to individual Business Application panel elements; and

17 in which for said modelled Business Application message a
18 Transaction Record is generated storing said Business
19 Application message description;

20 a User Interaction Graph generation step, in which the
21 sequence of Business Application messages as processed by said
22 Business Application is stored in at least one directed User
23 Interaction Graph.

1 25. The program storage device according to Claim 24 further
2 comprising:

3 a Business Application message transition generation step
4 in which a Business Application message transition action is
5 generated to launch the Business Application to process a next
6 Business Application panel after a current Business Application
7 panel according to the sequence within the User Interaction
8 Graph; and

9 in which said Business Application message transition
10 action is stored within the generated Transaction Record during
11 said Business Application message description generation step.

1 26. The program storage device according to Claim 24 wherein
2 said Business Application message description generation step
3 stores descriptive information on the individual panel elements
4 assembling said Business Application message with respect to

5 type or length or position or indications which of the panel
6 elements represent input and/or output elements within said
7 Transaction Record.

1 27. The program storage device according to Claim 24 wherein
2 said Business Application panel description is generated by
3 parsing and analyzing Business Application message
4 implementations of the system environment said Business
5 Application is implemented by interactions with a user of the
6 data processing system gathering required Business Application
7 panel description information.

1 28. The program storage device according to Claim 24 wherein
2 said Business Application message description generation step
3 incorporates indications on specific characteristics into the
4 generated Transaction Record encompassing
5 an Entry Transaction Record indication, characterizing a
6 Business Application messages required for an initial start of a
7 Business Application execution;
8 an External Transaction Record indication, characterizing a
9 Business Application message being part of a second User
10 Interaction Graph and thus describing a Business Application
11 message sequence with a branch from a first User Interaction
12 Graph to said second User Interaction Graph;
13 an interactive Transaction Record indication, indicating a
14 Business Application message representing a first Business
15 Application message of an execution unit of succeeding Business
16 Application messages within said User Interaction Graph
17 encompassing at least said interactive Transaction Record; and
18 a preemptive Transaction Record indication, indicating a
19 Business Application message being part of said execution unit
20 of succeeding Business Application messages and not being a
21 first Business Application message in said execution unit.

1 29. The program storage device according to Claim 28 in which
2 at least one Transaction Method is generated and provided to
3 execute an execution unit of succeeding Business Application
4 messages,

5 said Transaction Method is starting said execution of
6 Business Application messages with an interactive Transaction
7 Record;

8 said Transaction Method is proceeding said execution of
9 Business Application messages with all preemptive Transaction
10 Records succeeding said interactive Transaction Record within
11 the User Interaction Graph;

12 said Transaction Method is ending said execution of
13 Business Application messages with a next interactive
14 Transaction Record or with a last preemptive Transaction Record,
15 if no Transaction Record is succeeding said last preemptive
16 Transaction Record within the User Interaction Graph.

1 30. The program storage device according to Claims 29 wherein
2 said generated Transaction Method

3 encompasses as Transaction Method input parameters all
4 input elements of all Business Application messages modelled by
5 Transaction Records belonging to said execution unit and

6 encompasses as Transaction Method output parameters, all
7 output elements of all Business Application messages modelled by
8 Transaction Records belonging to said execution unit.

1 31. The program storage device according to Claim 23 extending
2 the generated Transaction Method by communication relevant
3 capabilities provided for

4 allowing the Transaction Method to be executed in a local
5 data processing system and

6 allowing the Transaction Method to communicate with a
7 remote data processing system via a computer network using
8 anyone of the available communication protocols and

9 allowing the Transaction Method to control execution of
10 said underlying Business Application on said remote data
11 processing system.

1 32. The program storage device according to claim 23 in which
2 the Transaction Method is generated as a method of a Transaction
3 Object class of object-oriented technology for encapsulating and
4 controlling said Business Application.

1 33. The program storage device according claim 23 in which said
2 Transaction Record is generated as Transaction Record class of
3 object-oriented technology.

0044042960
1 34. A computerized method of executing on a data processing
2 system at least one Business Application, wherein said Business
3 Application is panel-driven and offers its services interacting
4 with a user controlled by at least one Business Application
5 panel and wherein said Business Application processes succeeding
6 Business Application panels dependent on user interactions or
7 user specified data or the contents of any kind of data base the
8 Business Application is operating on, said computerized method
9 comprising:

10 a Transaction Method called from a program, said
11 Transaction Method is autonomously executing at least a part of
12 said Business Application without interacting with said user,
13 wherein said Transaction Method is autonomously providing
14 required input data to at least one sequence of succeeding
15 Business Application panels, and

16 wherein said Transaction Method is performing the required
17 activity for launching said Business Application to process,
18 after a current Business Application panel, a next Business
19 Application panel in said Business Application panel sequence
20 without interaction with said user.

1 35. The method according Claim 34 wherein said Transaction
2 Method includes handling Business Application messages with
3 respect to individual Business Application panel elements based
4 upon Transaction Records having Business Business Application
5 message descriptions and

6 wherein said Transaction Method launches the Business
7 Application to process, succeeding a current Business
8 Application panel, a next Business Application panel according
9 to a Business Application message transition action.

1 36. The method according Claim 34 wherein said Transaction
2 Method executes an execution unit of succeeding Business
3 Application messages;

4 starting said execution of Business Application messages
5 with an interactive Transaction Record indicating a Business
6 Application message representing a first Business Application
7 message of said execution unit of succeeding Business
8 Application messages;

9 proceeding said execution of Business Application messages
10 with all preemptive Transaction Records, specifying Business
11 Application messages being part of said execution unit of
12 succeeding Business Application messages and not being a first
13 Business Application message in said execution unit; and

14 ending said execution of Business Application messages with
15 a next interactive Transaction Record or with a last preemptive
16 Transaction Record, if no Transaction Record is succeeding said
17 last preemptive Transaction Record within said execution unit of
18 succeeding Business Application messages.

1 37. The method according to Claim 34 wherein said Transaction
2 Method is being executed in a local data processing system and
3 wherein said Transaction Method communicates with a remote
4 data processing system via a computer network and

5 wherein said Transaction Method controls execution of said
6 underlying Business Application on said remote data processing
7 system.

1 ~~38.~~ An apparatus for executing on a data processing system at
2 least one Business Application, wherein said Business
3 Application is panel-driven and offers its services interacting
4 with a user controlled by at least one Business Application
5 panel and wherein said Business Application processes succeeding
6 Business Application panels dependent on user interactions or
7 user specified data or the contents of any kind of data base the
8 Business Application is operating on, said apparatus comprising:

9 a Transaction Method means called from a program for
10 autonomously executing at least a part of said Business
11 Application without interacting with said user,

12 wherein said Transaction Method means includes means for
13 autonomously providing required input data to at least one
14 sequence of succeeding Business Application panels, and

15 wherein said Transaction Method means includes means for
16 performing the required activity for launching said Business
17 Application to process, after a current Business Application
18 panel, a next Business Application panel in said Business
19 Application panel sequence without interaction with said user.

1 39. The apparatus according Claim 38 wherein said Transaction
2 Method means includes means for handling Business Application
3 messages with respect to individual Business Application panel
4 elements based upon Transaction Records having Business Business
5 Application message descriptions, and

6 wherein said Transaction Method means launches the Business
7 Application to process, succeeding a current Business
8 Application panel, a next Business Application panel according
9 to a Business Application message transition action.

1 40. The apparatus according Claim 38 wherein said Transaction
2 Method means executes an execution unit of succeeding Business
3 Application messages, said execution unit comprising:

4 means for starting said execution of Business Application
5 messages with an interactive Transaction Record indicating a
6 Business Application message representing a first Business
7 Application message of said execution unit of succeeding
8 Business Application messages;

9 means for proceeding said execution of Business Application
10 messages with all preemptive Transaction Records, specifying
11 Business Application messages being part of said execution unit
12 of succeeding Business Application messages and not being a
13 first Business Application message in said execution unit; and

14 means for ending said execution of Business Application
15 messages with a next interactive Transaction Record or with a
16 last preemptive Transaction Record, if no Transaction Record is
17 succeeding said last preemptive Transaction Record within said
18 execution unit of succeeding Business Application messages.

1 41. The apparatus according to Claim 38 wherein said
2 Transaction Method means is being executed in a local data
3 processing system and

4 wherein said Transaction Method means communicates with a
5 remote data processing system via a computer network and

6 wherein said Transaction Method means controls execution of
7 said underlying Business Application on said remote data
8 processing system.

1 ~~42.~~ A program storage device readable by a machine tangibly
2 embodying at least one program of instructions executable by the
3 machine to perform method of executing on a data processing
4 system at least one Business Application, wherein said Business
5 Application is panel-driven and offers its services interacting
6 with a user controlled by at least one Business Application

panel and wherein said Business Application processes succeeding Business Application panels dependent on user interactions or user specified data or the contents of any kind of data base the Business Application is operating on, said computerized method comprising:

a Transaction Method called from a program, said Transaction Method is autonomously executing at least a part of said Business Application without interacting with said user, wherein said Transaction Method is autonomously providing required input data to at least one sequence of succeeding Business Application panels, and

wherein said Transaction Method is performing the required activity for launching said Business Application to process, after a current Business Application panel, a next Business Application panel in said Business Application panel sequence without interaction with said user.

43. The program storage device according Claim 42 wherein said Transaction Method includes handling Business Application messages with respect to individual Business Application panel elements based upon Transaction Records having Business Business Application message descriptions and

wherein said Transaction Method launches the Business Application to process, succeeding a current Business Application panel, a next Business Application panel according to a Business Application message transition action.

44. The program storage device according Claim 43 wherein said Transaction Method executes an execution unit of succeeding Business Application messages;

starting said execution of Business Application messages with an interactive Transaction Record indicating a Business Application message representing a first Business Application

7 message of said execution unit of succeeding Business
8 Application messages;
9 proceeding said execution of Business Application messages
10 with all preemptive Transaction Records, specifying Business
11 Application messages being part of said execution unit of
12 succeeding Business Application messages and not being a first
13 Business Application message in said execution unit; and
14 ending said execution of Business Application messages with
15 a next interactive Transaction Record or with a last preemptive
16 Transaction Record, if no Transaction Record is succeeding said
17 last preemptive Transaction Record within said execution unit of
18 succeeding Business Application messages.

00428001 45. The program storage device according to Claim 43 wherein
00428002 said Transaction Method is being executed in a local data
00428003 processing system and
00428004 wherein said Transaction Method communicates with a remote
00428005 data processing system via a computer network and
00428006 wherein said Transaction Method controls execution of said
00428007 underlying Business Application on said remote data processing
00428008 system.

METHODOLOGY FOR GENERATING
ACCESSING FUNCTIONS FOR PROGRAMMED EXECUTION
OF PANEL-DRIVEN BUSINESS APPLICATIONS

Abstract of the Disclosure

5 A method of providing access to Business Applications (BA)
executed on a data processing system wherein said BAs offer their
services interactively controlled by a multitude of BA panels and
wherein said BAs may display succeeding BA panels dependent on
user interactions, user specified data and the contents of any
10 kind of data base the BA is operating on. This inventive method
consists in two major steps. In a first step the individual
panels, the sequence of the panels as they are displayed by the
BA and the activities required to launch a BA to display a
succeeding panel are described. This step results in a directed
15 graph modelling the spectrum of panel interactions with a BA,
called a User Interaction Graph (UIG). By analyzing the UIG the
proposed method then generates in a second step procedures,
called Transaction Methods (TM). When called, the TM procedures
are capable of autonomously executing and controlling the BAs by
20 handling a sequence of BA panels. Based on input parameters
passed over to the TMs they autonomously fill the various BA
panels with the correct input information, initiate the required
activities for traversing through a certain panel sequence and
return the output information gathered during its execution.




FIG. 1




FIG. 2




FIG. 3

CDCIP11.CDCIP1._1 Browser Browser

5
6
7
8

Add Remove

Length Data Offset
11 4

401 Literal 402

Device Fieldname
PRODNA

Alignment Padding Character
☒ left 403 ☐ As Char
☐ right ☐ 32 As ASCII
☐ 64 As EBCDIC

OK Cancel Help

FIG. 4




FIG. 5

RecordSettings

Transitions to Successor Records

601 Successor
Exit [v] Remove

Source Successor
Exit [v] Copy From:

604 Action
ENTER [v]

Available Parameters

CDCIP1.STOCKQUA	[x]
CDCIP1.THRESHOL	[x]
CDCIP1.SYSMSG	[x]
CDCIP1.DGIA0000	[x]

Remove Add to Succ

Parameter for Selected Succ
CDCIP1.ACTION [v] 602

Actions Fields Connections Transition

OK Cancel Help

RecordSettings

SOURCE SUCCESSOR
Exit [v] Copy From:

Action
ENTER [v]

Available Parameters

CDCIP1.STOCKQUA	[x]
CDCIP1.THRESHOL	[x]
CDCIP1.SYSMSG	[x]
CDCIP1.DGIA0000	[x]

Remove Add to Succ

602 Parameter for Selected Succ
CDCIP1.ACTION [v] 607

603 Constant
E Clear

606 View

Actions Fields Connections Transition

OK Cancel Help

FIG. 6

Entry Settings

Transaction Parameters

Transaction Code: CDCIP1T (701)

Fields (702):

- Name
- PorNo
- Name

Length: 20

DpageOffset: 0

☐ Read Only

Literal/Global Constant: Clear

Buttons: Add, Delete

Bottom Buttons: OK, Cancel, Help

Tab Bar: Fields, Transitions

FIG. 7





FIG. 8



Legend

- Interactive Transaction Record
- Preemptive Transaction Record

FIG. 9




FIG. 10




FIG. 11

COMBINED DECLARATION FOR PATENT APPLICATION AND POWER OF ATTORNEY

(Includes Reference to PCT International Applications)

ATTORNEY'S DOCKET NUMBER

GE 995 047N

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name.

I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled:

METHODOLOGY FOR GENERATING ACCESSING FUNCTIONS FOR PROGRAMMED EXECUTION OF
PANEL-DRIVEN BUSINESS APPLICATIONS

the specification of which (check only one item below):

☐ is attached hereto.

☐ was filed as United States application

Serial No. _____

on _____

and was amended

on _____ (if applicable).

☒ was filed as PCT international application

Number, _____ PCT/EP 95/03234

on _____ August 16, 1995

and was amended under PCT Article 19

on _____ (if applicable).

I hereby state that I have reviewed and understand the contents of the above-identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose information which is material to the examination of this application in accordance with Title 37, Code of Federal Regulations, §1.56(a).

I hereby claim foreign priority benefits under Title 35, United States Code, §119 of any foreign application(s) for patent or inventor's certificate or of any PCT international application(s) designating at least one country other than the United States of America listed below and have also identified below any foreign application(s) for patent or inventor's certificate or any PCT international application(s) designating at least one country other than the United States of America filed by me on the same subject matter having a filing date before that of the application(s) of which priority is claimed:

PRIOR FOREIGN/PCT APPLICATION(S) AND ANY PRIORITY CLAIMS UNDER 35 U.S.C. 119:

COUNTRY (If PCT indicate "PCT")	APPLICATION NUMBER	DATE OF FILING (day, month, year)	PRIORITY CLAIMED UNDER 35 USC 119
			<input type="checkbox"/> YES <input type="checkbox"/> NO
			<input type="checkbox"/> YES <input type="checkbox"/> NO
			<input type="checkbox"/> YES <input type="checkbox"/> NO
			<input type="checkbox"/> YES <input type="checkbox"/> NO
			<input type="checkbox"/> YES <input type="checkbox"/> NO

Combined Declaration For Patent Application and Power of Attorney (Continued) (Includes Reference to PCT International Applications)				ATTORNEY'S DOCKET NUMBER GE 995 047N	
<p>I hereby claim the benefit under Title 35, United States Code, §120 of any United States application(s) or PCT international application(s) designating the United States of America that is/are listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in that/those prior application(s) in the manner provided by the first paragraph of Title 35, United States Code, §112, I acknowledge the duty to disclose material information as defined in Title 37, Code of Federal Regulations, §1.56(a) which occurred between the filing date of the prior application(s) and the national or PCT international filing date of this application:</p>					
PRIOR U.S. APPLICATIONS OR PCT INTERNATIONAL APPLICATIONS DESIGNATING THE U.S. FOR BENEFIT UNDER 35 U.S.C. 120:					
U.S. APPLICATIONS			STATUS (Check one)		
U.S. APPLICATION NUMBER	U.S. FILING DATE	PATENTED	PENDING	ABANDONED	
PCT APPLICATIONS DESIGNATING THE U.S.					
PCT APPLICATION NO	PCT FILING DATE	U.S. SERIAL NUMBERS ASSIGNED (if any)			
PCT/EP 95/03234	August 16, 1995				
<p>POWER OF ATTORNEY: As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) to prosecute this application and transact all business in the Patent and Trademark Office connected therewith. (List name and registration number)</p> <p>Augsburger, Reg. No. 24,227; Lawrence D. Cutter, Reg. No. 28,501; Marc A. Ehrlich, Reg. No. 39,966; Bernard M. Goldman, Reg. No. 17,959; Floyd A. Gonzalez, Reg. No. 26,732; William A. Kinnaman, Jr., Reg. No. 27,650; Lily Neff, Reg. No. 38,254; John A. Jordan, Reg. No. 24,655.</p>					
Send Correspondence to:			Direct Telephone Calls to:		
Lawrence D. Cutter, IBM Corporation, Intellectual Property Law, M/S P386, 522 South Road, Poughkeepsie, NY 12601-5400.			(name and telephone number) Lawrence D. Cutter (914) 433-1172		
201	FULL NAME OF INVENTOR	FAMILY NAME SCHMIDT	FIRST GIVEN NAME Andrea	SECOND GIVEN NAME none	
	RESIDENCE & CITIZENSHIP	CITY Bohlingen Stuttgart	STATE OR FOREIGN COUNTRY Germany	COUNTRY OF CITIZENSHIP Germany	
	POST OFFICE ADDRESS	POST OFFICE ADDRESS offenburger Str. Mühlrein 46A 37	CITY D-70180 Bohlingen Stuttgart	STATE & ZIP CODE/COUNTRY Germany	
202	FULL NAME OF INVENTOR	FAMILY NAME TWISSELMANN, Dr.	FIRST GIVEN NAME Ute	SECOND GIVEN NAME none	
	RESIDENCE & CITIZENSHIP	CITY Leimen Hildrizhausen	STATE OR FOREIGN COUNTRY Germany	COUNTRY OF CITIZENSHIP Germany	
	POST OFFICE ADDRESS	POST OFFICE ADDRESS Zähringer Str. 10 Brühlstrasse 16	CITY D-69181 Leimen Hildrizhausen	STATE & ZIP CODE/COUNTRY Germany	
203	FULL NAME OF INVENTOR	FAMILY NAME	FIRST GIVEN NAME	SECOND GIVEN NAME	
	RESIDENCE & CITIZENSHIP	CITY	STATE OR FOREIGN COUNTRY	COUNTRY OF CITIZENSHIP	
	POST OFFICE ADDRESS	POST OFFICE ADDRESS	CITY	STATE & ZIP CODE/COUNTRY	
<p>I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application or any patent issuing thereon.</p>					
SIGNATURE OF INVENTOR 201		SIGNATURE OF INVENTOR 202		SIGNATURE OF INVENTOR 203	
Ute Twisselmann		Andrea Schmidt			
DATE 4.7.96		DATE 9.7.96		DATE	